

Building Works Schedule

CODE	DESC	UNTM	MATL	LABR	PLNT	TOTL
F1082500	Walls	m2	26.43	11.87	0.44	38.74
F1082501	Walls, curved	m2	26.43	12.66	0.46	39.55
F1082530	Isolated casings	m2	26.43	15.04	0.55	42.02
F1082580	Closing cavities 50 mm wide, vertical	m	4.01	3.17	0.12	7.3
F1082600	Closing cavities 60 mm wide, vertical	m	4.01	3.17	0.12	7.3
F1082620	Closing cavities 75 mm wide, vertical	m	4.01	3.17	0.12	7.3
F1082650	Bonding to brickwork	m	0.95	4.75	0.17	5.87
F1084	Blockwork 100 mm thick to BS 6073 (crushing strength 20 N/mm ²) in cement mortar (1:6), flush pointing as work proceeds					
F1084700	Walls, facework one side	m2	26.43	13.46	0.49	40.38
F1084701	Walls, facework one side, curved	m2	26.43	15.04	0.55	42.02
F1084702	Walls, facework both sides	m2	26.43	15.83	0.58	42.84
F1084703	Walls, facework both sides, curved	m2	26.43	16.62	0.61	43.66
F1084750	Isolated casings, facework one side	m2	26.43	14.25	0.52	41.2
F1084800	Closing cavities 50 mm wide, vertical, facework	m	4.01	3.96	0.15	8.12
F1084820	Closing cavities 60 mm wide, vertical, facework	m	4.01	3.96	0.15	8.12
F1084840	Closing cavities 75 mm wide, vertical, facework	m	4.01	3.96	0.15	8.12
F1084860	Bonding to brickwork, facework one side	m	0.95	6.33	0.23	7.51
F1084861	Bonding to brickwork, facework both sides	m	0.95	7.91	0.29	9.15
F1086	Blockwork 150 mm thick to BS 6073 (crushing strength 20 N/mm ²) in cement mortar (1:6)					
F1086500	Walls	m2	36.91	12.66	0.46	50.03
F1086501	Walls, curved	m2	36.91	13.46	0.49	50.86
F1086530	Isolated casings	m2	36.91	15.04	0.55	52.5
F1086580	Closing cavities 50 mm wide, vertical	m	5.56	3.17	0.12	8.85
F1086600	Closing cavities 60 mm wide, vertical	m	5.56	3.17	0.12	8.85
F1086620	Closing cavities 75 mm wide, vertical	m	5.56	3.17	0.12	8.85
F1086650	Bonding to brickwork	m	1.26	6.33	0.23	7.82
F1088	Blockwork 150 mm thick to BS 6073 (crushing strength 20 N/mm ²) in cement mortar (1:6), flush pointing as work proceeds					
F1088700	Walls, facework one side	m2	36.91	15.04	0.55	52.5
F1088701	Walls, facework one side, curved	m2	36.91	16.62	0.61	54.14
F1088702	Walls, facework both sides	m2	36.91	17.41	0.64	54.96
F1088703	Walls, facework both sides, curved	m2	36.91	18.2	0.67	55.78
F1088750	Isolated casings, facework one side	m2	36.91	15.83	0.58	53.32
F1088800	Closing cavities 50 mm wide, vertical, facework	m	5.56	3.96	0.15	9.67
F1088820	Closing cavities 60 mm wide, vertical, facework	m	5.56	3.96	0.15	9.67
F1088840	Closing cavities 75 mm wide, vertical, facework	m	5.56	3.96	0.15	9.67
F1088860	Bonding to brickwork, facework one side	m	1.26	7.91	0.29	9.46
F1088861	Bonding to brickwork, facework both sides	m	1.26	10.29	0.38	11.93

Building Works Schedule

F30	Accessories/sundry items for brick/block/stone walling					
F3010	Sundries					
F3010050	Forming cavities in hollow walls 50 mm wide, galvanised steel butterfly wall ties to BS 1243 fig 1, spec 3.3, 4 nr/m2	m2	0.84	1.58	0	2.42
F3010051	Forming cavities in hollow walls 50 mm wide, stainless steel butterfly wall ties to BS 1243 fig 1, spec 3.6, 4 nr/m2	m2	1.08	1.58	0	2.66
F3010055	Forming cavities in hollow walls 50 mm wide, galvanised steel butterfly wall ties to BS 1243 fig 1, spec 3.3, 4 nr/m2, with cavity insulation of 25mm thick expanded polystyrene slabs fixed with clips to wall ties	m2	14.84	3.17	0	18.01
F3010056	Forming cavities in hollow walls 50 mm wide, stainless steel butterfly wall ties to BS 1243, spec 3.6, 4 nr/m2, with cavity insulation of 25mm thick expanded polystyrene slabs fixed with clips to wall ties	m2	15.08	3.17	0	18.25
F3010060	Forming cavities in hollow walls 60 mm wide, galvanised steel butterfly wall ties to BS 1243 fig 1, spec 3.3, 4 nr/m2	m2	0.84	1.58	0	2.42
F3010061	Forming cavities in hollow walls 60 mm wide, stainless steel butterfly wall ties to BS 1243 fig 1, spec 3.6, 4 nr/m2	m2	1.08	1.58	0	2.66
F3010062	Forming cavities in hollow walls 60 mm wide, galvanised steel butterfly wall ties to BS 1243 fig 1, spec 3.3, 4 nr/m2, with cavity insulation of 40 mm thick expanded polystyrene slabs fixed with clips to wall ties	m2	21.74	3.17	0	24.91
F3010063	Forming cavities in hollow walls 60 mm wide, stainless steel butterfly wall ties to BS 1243 fig 1, spec 3.6, 4 nr/m2 with cavity insulation of 40 mm thick expanded polystyrene slabs fixed with clips to wall ties	m2	21.98	3.17	0	25.15
F3010065	Forming cavities in hollow walls 75 mm wide, galvanised steel butterfly wall ties to BS 1243 fig 1, spec 3.3, 4 nr/m2	m2	0.72	1.58	0	2.3
F3010066	Forming cavities in hollow walls 75 mm wide, stainless steel butterfly wall ties to BS 1243 fig 1, spec 3.6, 4 nr/m2	m2	1.88	1.58	0	3.46
F3010068	Forming cavities in hollow walls 75 mm wide, galvanised steel butterfly wall ties to BS 1243 fig 1, spec 3.3, 4 nr/m2, with cavity insulation of 50 mm thick expanded polystyrene slabs fixed with clips to wall ties	m2	26.88	3.17	0	30.05
F3010069	Forming cavities in hollow walls 75 mm wide, stainless steel butterfly wall ties to BS 1243 fig 1, spec 3.6, 4 nr/m2, with cavity insulation of 50 mm thick expanded polystyrene slabs fixed with clips to wall ties	m2	28.04	3.17	0	31.21